

R/W COURSE DATA		
COURSE	BEARING	DISTANCE
A	N01°28'57"W	24.75
B	N89°42'15"E	229.48
C	N71°46'34"E	25.87
D	S17°42'27"E	24.75
E	S17°42'27"E	24.75
F	S73°22'17"W	18.33
G	S22°01'37"E	97.80
H	S16°19'46"E	56.81
I	S16°20'07"E	53.06
J	S73°39'55"W	24.75
K	S73°39'55"W	33.00
L	N42°55'35"W	255.37
M	N83°03'36"W	88.93
N	N01°28'57"W	33.00
O	S20°47'13"E	92.94
P	S01°53'59"E	63.57

SECTION CORNER TIES BY SOLBERGS & ASSOCIATES SURVEYING & DRAFTING, INC. LACROSSE, WISCONSIN.

COUNTY MONUMENT

P.I. STA. 9+28.18

JOHN L. LAYTON

P.T. STA. 11'A+03.91
END OF 'A' LINE RELOCATION

TEMPORARY LIMITED EASEMENT (T.L.E.) (0.05 ACRE)

DOUGLAS & KATHY PETERSON

PROJECT NUMBER	SHEET NO.
939335	

PLAN & PROFILE and PLAT OF RIGHT-OF-WAY
PETTINGER HILL ROAD
(BURNS CREEK TRIBUTARY CROSSING)
TOWN OF BURNS, LACROSSE COUNTY

BENCHMARKS			
NO.	STA.	DESCRIPTION	ELEV.
1	9+67	CHISELED CROSS ON N.E. WING WALL OF BRIDGE.	100.01
2	9+30	DBL. 20d. NAIL IN N.W. FACE OF 24" WILLOW.	97.91
3	9+76	DBL. 20d. NAIL IN N.W. FACE OF 24" DBL. TRK. WILLOW.	102.32

BRIAN K. & CARMEN M. MASHAK

CENTERLINE CURVE DATA

MAINLINE	'A' LINE
P.I.= STA. 9+28.18	P.I.= STA. 10'A+59.42
Δ = 75°09'00"	Δ = 36°55'41"
D = 20'00'	D = 40'00'
T = 220.42'	T = 47.83'
L = 375.75'	L = 92.32'
R = 286.48'	R = 143.24'

END RELOCATION ORDER
END PROJECT
STA. 11+00

LOCATED 2695.67 FEET EAST AND 199.11 FEET SOUTH OF THE NORTHWEST CORNER OF SECTION 36, T18N, R5W.

SCHEDULE OF LANDS & INTERESTS REQUIRED							
PARCEL NUMBER	OWNER(S)	INTEREST REQUIRED	TOTAL ACRES	T.L.E. ACRES	R/W ACRES REQUIRED		ACRES REMAINING
					NEW	EXISTING	
1	DOUGLAS & KATHY PETERSON	TLE	N/A	0.05	-	-	N/A
2	DONOVAN C. & LOIS HUBER	FEE	50	-	0.05	0.09	49.86
3	KENNETH P. & CARROL HUBER	FEE	258.89	-	0.38	0.06	258.53

BEGIN RELOCATION ORDER

BEGIN PROJECT
STA. 7+00

LOCATED 2400.94' EAST AND 23.33' NORTH OF NORTHWEST CORNER OF SEC. 36, T18N, R5W

EARTHWORK SUMMARY	
STA. 7+00 - STA. 11+00 & STA. 10'A+25 - STA. 11'A+00	UNCL. EXC. 1074 C.Y.
	FILL 1665 C.Y.
	SHRINKAGE 30%
	BORROW 1090 C.Y.

STA. 9+35, 1-CORRUGATED STEEL ARCH PIPE REQ'D.
112" HIGH x 75" HIGH x 56" LONG
CONCRETE MASONRY ENDWALLS REQ'D.
SKEW 4' LHF

OBSERVED WATER
EL. 91.48
(AT OUTLET)

STREAMBED
EL. 90.46

ACCEPTED FOR
TOWN OF BURNS

DATE _____ CHAIRMAN _____

ORIGINAL PLANS PREPARED BY:
MSA MID-STATE ASSOCIATES, INC.
1230 South Blvd, Baraboo, WI 53913

WISCONSIN
DANIEL H. WAGNER
E-19220
BARABOO
WISCONSIN
PROFESSIONAL ENGINEER

May 10, 1999 Date *Daniel H. Wagner* Signature