



**CURVE DATA**  
 Radius 1391.25'  
 Length 11.24'  
 Chord 11.24'  
 N 56°50'12\" W

**SURVEYOR'S CERTIFICATE**  
 I, Gary A. Watts, Registered Land Surveyor, hereby  
 certify that the above map and accompanying survey  
 are correct to the best of my knowledge and belief.

*Gary A. Watts*  
 Gary A. Watts S-1409

**PROPERTY DESCRIPTION**

All that part of the SW 1/4 of the SE 1/4 of Section 2,  
 T 15 N, R 5 W, Town of Washington, La Crosse County, Wisconsin,  
 described as follows:

Commence at the South 1/4 corner of said section 2; thence  
 N 04°58'44\" W, along the west line of said SE 1/4, 193.02 feet to  
 the intersection with the northerly right of way line of S.T.H. 33, the  
 point of beginning; continue thence N 04°58'44\" W 344.75 feet;  
 thence S 57°04'05\" E 181.50 feet; thence S 62°53'42\" E  
 265.17 feet; thence S 26°35'55\" W 136.36 feet to the northwesterly  
 right of way line of C.T.H. \"JB\"; thence S 52°22'43\" W, along said  
 right of way line, 164.78 feet to the northerly right of way line of  
 S.T.H. 33; thence N 57°04'05\" W, along said right of way line,  
 167.77 feet to a point of curvature; thence Northwesterly 32.42 feet  
 along the arc of a curve to the right whose radius is 1391.25 feet  
 and whose chord bears N 56°24'02\" W 32.42 feet to the point of  
 beginning. Except therefrom a strip of land one rod wide running North  
 and South, the west line of said strip being the west line of aforesaid parcel.  
 This parcel contains 87,542 square feet, 2.01 acres, more  
 or less.

	REVISIONS	DAVY ENGINEERING CO. LA CROSSE — WISCONSIN		PROJECT NUMBER 7555-10 SHEET 1 OF 1
		ST. PETERS PARISH		
		BALLPARK		
		MIDDLE RIDGE WISCONSIN		
NOTED NO. 600	DATE MAY 1983	DRAWN G. A. W.	CHECKED	SCALE 1\" = 40'